AIR HANDLING UNITS

UNIT NO.	SERVICE	UNIT: TYPE	SYSTEM TYPE	CFM OF STD. AIR	MIN. CFM OF O.A.	MAX. CFM OF O.A.	SUPPLY CONN. SIZE	EXT. S.P. IN IN. WATER	NO. OF FANS	MOTOR HP	FAN WHEEL TYPE	DRIVE TYPE	MOTOR TYPE	MAX VFD HZ.	FILTER TYPE	VOLUME CONTROL	SUPPORT	HEATING COIL: MAX. FACE VEL.	ENT. AIR TEMP.	LV. AIR TEMP.	ENT. H2O TEMP.	LV. H2O TEMP.	% PROP. GLYCOL	MAX. H2O P.D. IN FT.	GPM	BRANCH PIPE SIZE	COOLING COIL: MAX. FACE VEL.	ENT. AIR D.B.	ENT. AIR W.B.	LV. AIR D.B.	LV. AIR W.B.	ENT. H20 TEMP.	LV. H20 TEMP.	% PROP. GLYCOL	MAX. H2O P.D. IN FT.	GPM	BRANCH PIPE SIZE	DESIGN DIMENSIONS: LENGTH	WIDTH	HEIGHT	WEIGHT LBS.	MANUF. MODEL
AHU-5	GYM & WRESTLING	HORIZ.	SZVAV	15,500	1,000	3,900	56x34	1.5	1	20	PLENUM	DIRECT	ODP	70 Hz	2" MERV 13	VFD	CONC. PAD	550	44 °F	70 °F	160 °F	120 °F	0	10	21.9	2"	550	78 °F	67.8 °F	53 °F	52.4 °F	44 °F	57 °F	35	25	124	3"	15' - 2"	8' - 2"	5' - 0"	5100	DAIKIN CAH-030
AHU-6	GYM	HORIZ.	SZVAV	12,500	500	8,500	38x38	1.5	1	15	PLENUM	DIRECT	ODP	70 Hz	2" MERV 13	VFD	CONC. PAD	550	12 °F	95 °F	160 °F	120 °F	0	10	56.3	2 1/2"	550	79.3 °F	69.2 °F	53 °F	52.4 °F	44 °F	57 °F	35	25	112	3"	15' - 4"	7' - 2"	5' - 0"	4800	DAIKIN CAH-025
AHU-10	OFFICES	HORIZ.	VAV	10,000	1,520	1,520	46x28	3	1	15	PLENUM	DIRECT	ODP	70 Hz	2" MERV 13	VFD	STEEL STAND	550	55 °F	70 °F	160 °F	120 °F	0	10	8.2	1 1/4"	550	76.8 °F	64.7 °F	53 °F	52.4 °F	44 °F	57 °F	35	25	62	2 1/2"	12' - 2"	6' - 10"	4' - 4"	3600	DAIKIN CAH-021
AHU-11	CLASSROOMS	HORIZ.	VAV	25,000	4,100	7,500	70x40	2.5	1	30	PLENUM	DIRECT	ODP	70 Hz	2" MERV 13	VFD	CONC. PAD	550	43 °F	70 °F	160 °F	120 °F	0	10	36.6	2"	550	77.6 °F	65.9 °F	53 °F	52.4 °F	44 °F	57 °F	35	25	172	4"	18' - 2"	10' - 0"	6' - 8"	8500	DAIKIN CAH-050
AHU-B2	POOL LOCKERS	HORIZ.	SZVAV	2,100	2,100	2,100	18x18	1.5	1	2	PLENUM	DIRECT	ODP	70 Hz	2" MERV 13	VFD	CONC. PAD	550	-10 °F	100 °F	160 °F	120 °F	35	10	12.8	1 1/4"												9' - 8"	4' - 4"	2' - 6"	1000	DAIKIN CAH-006

NOTE: AHU-B2 IS UNDER ALTERNATE BID H1

ROOF MOUNTED ENERGY RECOVERY UNITS

UNIT NO.	SERVICE	SUPPLY SIDE: CFM OF STD. AIR	MIN. CFM OF O.A.	MAX. CFM OF O.A.	EXT. S.P. IN IN. WATER	WINTER E.A.T. D.B.	WINTER E.A.T. W.B.	WINTER L.A.T. D.B.	WINTER L.A.T. W.B.	SUMMER E.A.T. D.B.	SUMMER E.A.T. W.B.	SUMMER L.A.T. D.B.	SUMMER L.A.T. W.B.	MOTOR HP	FAN WHEEL TYPE	MOTOR TYPE	COOLING COIL: E.A.T. D.B.	E.A.T. W.B.	L.A.T. D.B.	L.A.T. W.B.	ENT. H20 TEMP.	LV. H20 TEMP.	GPM	BRANCH PIPE SIZE	% PROP. GLYCOL	TOT. CAP. MBH	HEATING COIL: ENT. AIR TEMP.	LV. AIR TEMP.	ENT. H20 TEMP.	LV. H20 TEMP.	GPM	BRANCH PIPE SIZE	% PROP. GLYCOL	TOT. CAP. MBH	EXHAUST SIDE: MAX. CFM OF EXH. AIR	EXT. S.P. IN IN. WATER	WINTER E.A.T. D.B.	WINTER E.A.T. W.B.	SUMMER E.A.T. D.B.	SUMMER E.A.T. W.B.	MOTOR HP	FAN WHEEL TYPE	MOTOR TYPE	INTEGRAL VFD	MAX VFD HZ.	FILTER TYPE	ENERGY WHEEL	SUPPORT	DESIGN DIMENSIONS: WIDTH	LENGTH	HEIGHT	WEIGHT LBS.	MANUF. MODEL
RERU-1	AUTOS LAB C121	3,000	300	3,000	0.75	-15 °F	-15 °F	40.8 °F	33.7 °F	87 °F	75 °F	77.8 °F	66 °F	5	PLENUM	ODP	77.8 °F	66 °F	55 °F	54 °F	44 °F	57 °F	15	1 1/2"	35	81.6	40 °F	95 °F	160 °F	120 °F	9	1 1/4"	0	180	3,000	0.75	70 °F	52 °F	75 °F	62 °F	3	PLENUM	ODP	YES	70	MERV 13	YES	ROOF CURB	6' - 1"	12' - 7"	5' - 5"	2,000	AAON
RERU-2	EXISTING FITNESS	1,725	1,725	1,725	1.5	-15 °F	-15 °F	45.1 °F	37 °F	87 °F	75 °F	78.3 °F	66.4 °F	3	PLENUM	ODP	78.3 °F	66.4 °F	55 °F	54 °F	44 °F	57 °F	12.5	1 1/4"	35	58	45 °F	70 °F	160 °F	120 °F	5	1"	0	59	1,725	1	70 °F	52 °F	75 °F	62 °F	2	PLENUM	ODP	YES	70	MERV 13	YES	ROOF CURB	4' - 10"	11' - 2"	5' - 0"	1,300	AAON

BLOWER COIL UNITS

UNIT NO.	SERVICE	UNIT: TYPE	CFM OF STD. AIR	CFM OF O.A.	EXT. S.P. IN IN. WATER	NO. OF FANS	NO. OF MOTORS	MOTOR HP	DRIVE	MOTOR TYPE	FILTER TYPE	SUPPORT	HEATING COIL: ENT. AIR D.B.	LV. AIR D.B.	ENT. H20 TEMP.	LV. H20 TEMP.	% PROP. GLYCOL	GPM	BRANCH PIPE SIZE	COOLING COIL: ENT. AIR D.B.	ENT. AIR W.B.	LV. AIR D.B.	LV. AIR W.B.	ENT. H20 TEMP.	LV. H20 TEMP.	% PROP. GLYCOL	GPM	BRANCH PIPE SIZE	VIBRATION ISOLATORS: TYPE	MIN. STATIC DEFLECT.	MANUF. MODEL
BCU-1	WOODS LAB C131	HORIZ.	3,700	370	1	2	2	4.42	DIRECT	ECPM	2" MERV 13	SUSPENDED	58 °F	95 °F	160 °F	120 °F	0	7.5	1 1/4"	76.4 °F	65 °F	58.9 °F	58.4 °F	44 °F	57 °F	35	12.5	1 1/4"	D	0' - 1"	DAIKIN BCHE
BCU-2	METALS LAB C120	HORIZ.	2,800	280	1	1	1	4.42	DIRECT	ECPM	2" MERV 13	SUSPENDED	58 °F	95 °F	160 °F	120 °F	0	5.7	1"	76.4 °F	65 °F	59.1 °F	58.4 °F	44 °F	57 °F	35	9.4	1 1/4"	D	0' - 1"	DAIKIN BCHE
BCU-3	ROBOTICS C116	HORIZ.	1,725	225	1	1	2	0.75	DIRECT	ECPM	2" MERV 13	SUSPENDED	57 °F	90 °F	160 °F	120 °F	0	3.1	3/4"	76.6 °F	65.2 °F	59.2 °F	58.5 °F	44 °F	57 °F	35	5.9	1"	D	0' - 1"	DAIKIN BCHD
BCU-4	KITCHEN/SERVERY	HORIZ.	2,800	280	1	1	1	4.42	DIRECT	ECPM	2" MERV 13	SUSPENDED	58 °F	95 °F	160 °F	120 °F	0	5.7	1"	76.4 °F	65 °F	57.6 °F	57.3 °F	44 °F	57 °F	35	10.9	1 1/4"	D	0' - 1"	DAIKIN BCHE

FAN COIL UNITS

UNIT NO.	SERVICE	UNIT: TYPE	CFM OF STD. AIR	CFM OF O.A.	EXT. S.P. IN IN. WATER	NO. OF FANS	MOTOR TYPE	NO. OF MOTORS	MOTOR HP EA.	DRIVE	RECESS	HEATING COIL: TOT. CAP. MBH	ENT. AIR D.B.	LV. AIR D.B.	ENT. H2O TEMP.	LV. H2O TEMP.	% PROP. GLYCOL	GPM	BRANCH PIPE SIZE	COOLING COIL: TOT. MBH @ 80/67 E.A.T.	ENT. H2O TEMP.	LV. H2O TEMP.	% PROP. GLYCOL	GPM	BRANCH PIPE SIZE	MANUF. MODEL
FC-1	SMALL ANIMALS C128	HC	450	100	0.5	1	ECPM	1	0.25	DIRECT	0' - 10"	22.5	49 °F	95 °F	160 °F	140 °F	0	2.3	3/4"	13.5	44 °F	57 °F	35	2.3	3/4"	DAIKIN FCHH
FC-2	AQUAPONICS C130	HC	500	100	0.5	1	ECPM	1	0.25	DIRECT	0' - 10"	24.4	50 °F	95 °F	160 °F	140 °F	0	2.5	3/4"	15	44 °F	57 °F	35	2.5	3/4"	DAIKIN FCHH
FC-3	METALS CLASSROOM C118	HC	800	225	0.5	2	ECPM	1	0.25	DIRECT	0' - 10"	44.3	44 °F	95 °F	160 °F	140 °F	0	4.5	1"	24	44 °F	57 °F	35	4	1"	DAIKIN FCHH

GAS FIRED MAKE-UP AIR UNITS

UNIT NO.	SERVICE	CFM OF STD. AIR	CFM OF O.A.	EXT. S.P. IN IN. WATER	HEATING SECTION: GAS INPUT MBH	GAS OUTPUT MBH	BURNER TYPE	GAS TYPE	GAS PRESS. IN PSIG	MOTOR HP	FAN TYPE	MOTOR TYPE	SUPPORT	DESIGN DIMENSIONS: LENGTH	WIDTH	HEIGHT	WEIGHT LBS.	MANUF. MODEL
MUA-1	METALS LAB C120	14,500	14,500	0.5	1,700	1,565	MODULATING	NAT. GAS	5	10	PLENUM	ODP	ROOF CURB	171"	52"	49"	1600	GREENHECK DGX
MUA-2	WOODS LAB C131	6,500	6,500	0.5	767	705	MODULATING	NAT. GAS	5	5	PLENUM	ODP	ROOF CURB	160"	44"	46"	1200	GREENHECK DGX

PUMPS

UNIT NO.	SERVICE	PUMP: SIZE	GPM	FEET OF WATER HEAD	MOTOR HP	MOTOR RPM	MOTOR TYPE	VFD	SUPPORT	% PROP. GLYCOL	VIBRATION ISOLATORS: TYPE	VIBRATION ISOLATORS: MIN. STATIC DEFLECT.	SUCTION DIFFUSER: INLET SIZE	SUCTION DIFFUSER: OUTLET SIZE	START-UP STRAINER	MANUF. MODEL
P-1	HOT WATER SYSTEM	3 X 4	450	90	15	1800	ODP	YES	CONC. PAD	0	IB	0' - 1"	5"	4"	YES	B&G SERIES e1532
P-2	P-1 STANDBY	3 X 4	450	90	15	1800	ODP	YES	CONC. PAD	0	IB	0' - 1"	5"	4"	YES	B&G SERIES e1532
P-3	CHILLER PRIMARY	5 X 6	550	40	10	1200	ODP	YES	CONC. PAD	35	IB	0' - 1"	6"	6"	YES	B&G SERIES e1532
P-4	P-3 STANDBY	5 X 6	550	40	10	1200	ODP	YES	CONC. PAD	35	IB	0' - 1"	6"	6"	YES	B&G SERIES e1532
P-5	CHILLED WATER SYSTEM	3 X 4	550	130	25	3600	ODP	YES	CONC. PAD	35	IB	0' - 1"	6"	4"	YES	B&G SERIES e1532
P-6	P-5 STANDBY	3 X 4	550	130	25	3600	ODP	YES	CONC. PAD	35	IB	0' - 1"	6"	4"	YES	B&G SERIES e1532

NOTE: SCHEDULED CHILLED WATER PUMP HEAD ALREADY INCLUDES FACTORS FOR GLYCOL.

BOOSTER COILS

UNIT NO.	SERVICE	WIDTH	HEIGHT	CFM OF STD. AIR	MAX. FACE VEL. H.C.	ENT. AIR TEMP.	LV. AIR TEMP.	ENT. H2O TEMP.	LV. H2O TEMP.	ACC. DOOR SIZE	% PROP. GLYCOL	MAX. H2O P.D. IN FT.	GPM	BRANCH PIPE SIZE	MANUF. MODEL
BC-1	FITNESS A134	16	9	475	475	55 °F	85 °F	160 °F	140 °F	6" x 6"	0	10	1.6	1/2"	DAIKIN
BC-2	CLASSROOM A126	16	9	525	525	55 °F	85 °F	160 °F	140 °F	6" x 6"	0	10	1.7	1/2"	DAIKIN
BC-3	FITNESS A133	16	9	550	550	55 °F	85 °F	160 °F	140 °F	6" x 6"	0	10	1.8	1/2"	DAIKIN
BC-4	OFFICE A121	12	6	175	350	55 °F	85 °F	160 °F	140 °F	6" x 6"	0	10	0.6	1/2"	DAIKIN
BC-5	EXISTING AUDITORIUM	48	36	10,000	850	55 °F	90 °F	160 °F	120 °F	24" x 24"	0	10	19	1 1/2"	DAIKIN
BC-6	EXISTING AUDITORIUM	60	42	15,000	850	55 °F	90 °F	160 °F	120 °F	24" x 24"	0	10	28.5	2"	DAIKIN
BC-7	EXISTING GYM	60	30	9,500	760	55 °F	90 °F	160 °F	120 °F	24" x 24"	0	10	18.1	1 1/2"	DAIKIN
BC-8	EXISTING WRESTLING	48	24	6,000	750	55 °F	90 °F	160 °F	120 °F	24" x 24"	0	10	11.4	1 1/4"	DAIKIN

CABINET HEATERS

UNIT NO.	SERVICE	TYPE	CAP. MBH	CFM OF STD. AIR	MOTOR HP	DRIVE	MOTOR TYPE	SPEED	RECESS	ELEV. ABOVE FIN. FL.	ENT. H20 TEMP.	LV. H2O TEMP.	% PROP. GLYCOL	GPM	BRANCH PIPE SIZE	MANUF. MODEL
CH-1	CORRIDOR A109B	CR	33.7	420	0.2	DIRECT	ECPM	3	0' - 10"	9' - 6"	160 °F	140 °F	0	4.7	1"	RITTLING 04
CH-2	CORRIDOR A109	IW	33.7	420	0.2	DIRECT	ECPM	3	0' - 0"	0' - 8"	160 °F	140 °F	0	4.7	1"	RITTLING 04
CH-3	VESTIBULE C117	IW	33.7	420	0.2	DIRECT	ECPM	3	0' - 0"	0' - 8"	160 °F	140 °F	0	4.7	1"	RITTLING 04
CH-4	STORAGE C129D	CR	17.9	220	0.2	DIRECT	ECPM	3	0' - 10"	8' - 0"	160 °F	140 °F	0	2.5	3/4"	RITTLING 02

DUST COLLECTOR

UNIT NO.	SERVICE	CFM OF STD. AIR	EXT. S.P. IN IN. WATER	MOTOR HP	DRIVE	DUST RECEIVER	SYSTEM TYPE	MAX DUST KST	SUPPORT	MANUF. MODEL
DC-1	WOODS LAB C131	7,100	9	30	BELT	(2) 55 GAL. DRUM	WOODS	185	STRUCT. STEEL STAND ON CONC. PAD	AQS DCS-30

UNIT HEATERS

UNIT NO.	SERVICE	TYPE	CAP. MBH	CFM OF STD. AIR	MOTOR HP	MOTOR RPM	SPEED	DIFFUSER	ENT. H2O TEMP.	LV. H2O TEMP.	% PROP. GLYCOL	GPM	BRANCH PIPE SIZE	ELEV. ABOVE FIN. FL.	MANUF. MODEL
UH-1	WOODS LAB C131	HORIZ.	140.4	4,590	0.5	1075	1	HORIZ.	160 °F	120 °F	0	11.5	1 1/2"	10' - 0"	MODINE HC 290
UH-2	AUTOS LAB C121	HORIZ.	140.4	4,590	0.5	1075	1	HORIZ.	160 °F	120 °F	0	11.5	1 1/2"	10' - 0"	MODINE HC 290
UH-3	METALS LAB C120	HORIZ.	80.4	3,240	0.33	1075	1	HORIZ.	160 °F	120 °F	0	6.6	1 1/4"	10' - 0"	MODINE HC 165
UH-4	RECEIVING A108	HORIZ.	51.4	2,010	0.13	1625	1	HORIZ.	160 °F	120 °F	0	8.4	1 1/4"	10' - 0"	MODINE HC 108

GENERAL NOTES:

A. THE MECHANICAL CONTRACTOR IS REQUIRED TO VISIT THE PREMISES AND TAKE NOTE OF ALL EXISTING CONDITIONS WHICH MAY AFFECT HIS WORK AND HE SHALL BE RESPONSIBLE FOR KNOWLEDGE OF SAME IN THE PREPARATION OF HIS BID. LACK OF INFORMATION ON EXISTING CONDITIONS SHALL NOT BE ALLOWED AS A VALID CAUSE FOR ADDITIONAL COMPENSATION.

B. ROUTE ALL NEW PIPING AND DUCTWORK AS REQUIRED TO AVOID CONFLICTS WITH EXISTING PIPING, CONDUIT, STRUCTURE, LIGHTING, ETC. PROVIDE ALL OFFSETS, ELBOWS, ETC. AS REQUIRED TO CONNECT BETWEEN POINTS INDICATED.

C. MECHANICAL CONTRACTOR SHALL VERIFY EXISTING CURRENT CHARACTERISTICS AT JOB SITE PRIOR TO ORDERING EQUIPMENT.

D. MECHANICAL CONTRACTOR SHALL COORDINATE EXACT OUTLET AND GRILLE LOCATIONS WITH THE FINAL LIGHTING LAYOUT.

E. ELECTRICAL, STRUCTURAL, PLUMBING, ETC. REQUIREMENTS FOR THE EQUIPMENT MANUFACTURER LISTED ON THE SCHEDULE IS REFLECTED ON THE DOCUMENTS OF OTHER TRADES. ANY MODIFICATIONS NECESSARY TO ACCOMMODATE A MANUFACTURER OTHER THAN THAT LISTED IS THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR.

F. THE MECHANICAL CONTRACTOR SHALL COORDINATE CONSTRUCTION PHASING WITH THE GENERAL CONTRACTOR AND OWNER. PROVIDE ALL TEMPORARY PIPING, DUCTWORK, VENTILATION, CONTROLS, ETC. AS REQUIRED TO ACCOMMODATE CONSTRUCTION PHASES.

G. THE WORK SHOWN ON THESE CONSTRUCTION DRAWINGS IS TO BE INSTALLED IN ACCORDANCE WITH THE SPECIFICATIONS INCLUDED IN DIVISIONS 23 AND 25 OF THE COMPLETE CONTRACT DOCUMENTS.

EQUIPMENT BRANCH PIPE SIZING TABLE

NOTE: IN THE EVENT THERE IS A DISCREPANCY BETWEEN THE EQUIPMENT SCHEDULE AND THE PIPE SIZING TABLE, THE PIPE SIZING TABLE SHALL TAKE PRECEDENT.

SIZE	GPM
1/2"	0 - 1.6
3/4"	1.7 - 3.5
1"	3.6 - 6.5
1 1/4"	6.6 - 14.0
1 1/2"	14.1 - 21.0
2"	21.1 - 41.0
2 1/2"	41.1 - 66.0
3"	66.1 - 130.0
4"	130.1 - 260.0
5"	260.1 - 480.0
6"	480.1 - 800.0
8"	800.1 - 1550.0
10"	1550.1 - 2500.0
12"	2500.1 - 3600.0

GRILLES AND DIFFUSERS

TAG NO.	SERVICE	NECK SIZE	DUCT CONN. SIZE	VOLUME DAMPER LOCATION	AIR PATTERN	MANUF. MODEL
EG-1	EXHAUST GRILLE	12x12	-	DUCT TAKEOFF	EGGCRATE	PRICE 80
EG-2	EXHAUST GRILLE	16x16	-	DUCT TAKEOFF	EGGCRATE	PRICE 80
EG-3	EXHAUST GRILLE	22x22	-	DUCT TAKEOFF	EGGCRATE	PRICE 80
RG-1	RETURN GRILLE	12x12	-	DUCT TAKEOFF	EGGCRATE	PRICE 80
RG-2	RETURN GRILLE	16x16	14"Ø	DUCT TAKEOFF	EGGCRATE	PRICE 80
RG-3	RETURN GRILLE	22x22	-	DUCT TAKEOFF	EGGCRATE	PRICE 80
RG-4	SIDEWALL RETURN GRILLE	12x12	-	DUCT TAKEOFF	45°	PRICE 530
RG-5	SIDEWALL RETURN GRILLE	40x14	-	DUCT TAKEOFF	45°	PRICE 530
SG-1	PLAQUE DIFFUSER	24x24	8"Ø	DUCT TAKEOFF	4-WAY	PRICE SPD
SG-2	PLAQUE DIFFUSER	24x24	10"Ø	DUCT TAKEOFF	4-WAY	PRICE SPD
SG-3	PLAQUE DIFFUSER	24x24	12"Ø	DUCT TAKEOFF	4-WAY	PRICE SPD
SG-4	SIDEWALL SUPPLY GRILLE	24x4	-	DUCT TAKEOFF	22.5°	PRICE 520
SG-5	SIDEWALL SUPPLY GRILLE	10x8	-	DUCT TAKEOFF	22.5°	PRICE 520
SG-6	SIDEWALL SUPPLY GRILLE	16x8	-	DUCT TAKEOFF	22.5°	PRICE 520
SG-7	SIDEWALL SUPPLY GRILLE	10x10	-	DUCT TAKEOFF	22.5°	PRICE 520
SG-8	SIDEWALL SUPPLY GRILLE	18x12	-	DUCT TAKEOFF	22.5°	PRICE 520
TG-1	TRANSFER GRILLE	12x12	-	-	EGGCRATE	PRICE 80
TG-2	TRANSFER GRILLE	22x22	-	-	EGGCRATE	PRICE 80
TG-3	SIDEWALL TRANSFER GRILLE	12x12	-		45°	PRICE 530

SYMBOLS

HS	HOT WATER SUPPLY
HR	HOT WATER RETURN
CS	CHILLED WATER SUPPLY
CR	CHILLED WATER RETURN
G	GAS
PCS	PRIMARY CHILLED WATER SUPPLY
PCR	PRIMARY CHILLED WATER RETURN
	BALL VALVE
	BUTTERFLY VALVE
CBV	CALIBRATED BALANCING VALVE
	FLOW DIRECTION
	GAS VALVE
	UNION
	FLEXIBLE DUCT
VD	MANUAL VOLUME DAMPER
CD	CONTROL DAMPER WITH ACCESSIBLE DUCT ACCESS DOOR
CDA	COMBINATION CONTROL DAMPER AND AIR MEASURING STATION WITH ACCESSIBLE DUCT ACCESS DOOR
FD	FIRE DAMPER WITH ACCESSIBLE DUCT ACCESS DOOR
FSD	COMBINATIONS SMOKE/FIRE DAMPER WITH ACCESSIBLE DUCT ACCESS DOOR
	ACOUSTICAL INSULATION LINING ON INSIDE OF DUCT. LISTED DIMENSION IS CLEAR INSIDE DIMENSION.
	TURNING VANES
	BRANCH TAKE-OFF
MD	LOW PRESSURE FLEX. DUCT FITTING WITH MANUAL VOLUME DAMPER
UC	1" DOOR UNDERCUT. DOOR UNDERCUT BY GEN. CONTR.
T	ROOM SENSOR OR THERMOSTAT
S	REMOTE MOUNTED SWITCH
	CONNECT TO EXISTING DUCTWORK OR PIPING. FIELD VERIFY EXACT REQUIREMENTS.
	STATIC PRESSURE SENSOR

HVAC SHEET INDEX		HVAC SHEET INDEX	
	MSA JOB No. 00377241		MSA JOB No. 00377241
H0.1	SCHEDULES	H2.2A	UNIT A - SECOND FLOOR DUCTWORK PLAN
H0.2	SCHEDULES	H2.2B	UNIT B - SECOND FLOOR DUCTWORK PLAN
H1.1	OVERALL FIRST FLOOR DEMOLITION PLAN	H2.2C	UNIT C - SECOND FLOOR DUCTWORK PLAN
H1.1A	UNIT A - FIRST FLOOR DEMOLITION PLAN	H2.2F	UNIT F - SECOND FLOOR DUCTWORK PLAN
H1.1B	UNIT B - FIRST FLOOR DEMOLITION PLAN	H2.2G	UNIT G - SECOND FLOOR DUCTWORK PLAN
H1.1C	UNIT C - FIRST FLOOR DEMOLITION PLAN	H2.3	OVERALL ROOF PLAN
H1.1F	UNIT F - FIRST FLOOR DEMOLITION PLAN	H3.1A	UNIT A - FIRST FLOOR PIPING PLAN
H1.2	OVERALL SECOND FLOOR DEMOLITION PLAN	H3.1B	UNIT B - FIRST FLOOR PIPING PLAN
H1.2A	UNIT A - SECOND FLOOR DEMOLITION PLAN	H3.1C	UNIT C - FIRST FLOOR PIPING PLAN
H1.2B	UNIT B - SECOND FLOOR DEMOLITION PLAN	H3.1F	UNIT F - FIRST FLOOR PIPING PLAN
H1.2F	UNIT F - SECOND FLOOR DEMOLITION PLAN	H3.2A	UNIT A - SECOND FLOOR PIPING PLAN
H1.2G	UNIT G - SECOND FLOOR DEMOLITION PLAN	H3.2B	UNIT B - SECOND FLOOR PIPING PLAN
H1.3	OVERALL ROOF DEMOLITION PLAN	H3.2F	UNIT F - SECOND FLOOR PIPING PLAN
H2.1	OVERALL FIRST FLOOR PLAN	H3.2G	UNIT G - SECOND FLOOR PIPING PLAN
H2.1A	UNIT A - FIRST FLOOR DUCTWORK PLAN	H4.1	GYM MECHANICAL ROOM PLANS
H2.1B	UNIT B - FIRST FLOOR DUCTWORK PLAN	H4.2	WOODS AND AUTO MECHANICAL MEZZANINE PLANS
H2.1C	UNIT C - FIRST FLOOR DUCTWORK PLAN	H4.3	AUDITORIUM & AQUATICS MECHANICAL ROOM PLANS
H2.1F	UNIT F - FIRST FLOOR DUCTWORK PLAN	H6.1	DETAILS
H2.2	OVERALL SECOND FLOOR PLAN	H6.2	DETAILS



12/19/2025

BRAY ARCHITECTS
Milwaukee
829 South 1st Street
Milwaukee, Wisconsin 53204
T: 414.226.0200
Sheboygan • Davenport
Moline • Saint Paul
www.brayarch.com

ENGINEERING DESIGN BY MSA
(800) 362-4505 • www.msa-ps.com

Project Title:
ADDITION AND RENOVATIONS
WHITEWATER HIGH SCHOOL
WHITEWATER UNIFIED SCHOOL DISTRICT
534 S. ELIZABETH
WHITEWATER, WI 53190

ISSUANCES + REVISIONS:

	DATE	DESCRIPTION

Issued for:
CONSTRUCTION DOCUMENTS
12/19/2025

Project Number:
3705

Sheet Title:
SCHEDULES

Sheet Number:
H0.1

© 2024 Bray Associates Architects, Inc.

Autodesk Docs://3705 - Whitewater Unified School District Facility Master Planning 20240937241_Whitewater High School_HVAC_R24.rvt
12/18/2025 3:50:53 PM

UTILITY EXHAUST FANS

UNIT NO.	SERVICE	CFM OF STD. AIR	MAX. O.V.	EXT. S.P. IN IN. WATER	MOTOR HP	DRIVE	MOTOR TYPE	FAN DIA.	FAN WHEEL TYPE	FAN ROTATION	FAN DISCHARGE	W.P. COVER	DAMPER	SUPPORT	VIBRATION ISOLATORS		MANUF. MODEL
															TYPE	MIN. STATIC DEFLECT.	
UE-1	WELDING EXHAUST	4,900	2650	2.5	5	BELT	ODP	18"	AF	CW	UBD	YES	MOTORIZED	EQ. SUPP. RAILS	C	1"	COOK CPS-A-180
UE-2	WELDING EXHAUST	4,200	2300	2.5	3	BELT	ODP	18"	AF	CW	UBD	YES	MOTORIZED	EQ. SUPP. RAILS	C	1"	COOK CPS-A-180
UE-3	PLASMA TABLE HOOD	3,600	2300	1.5	2	BELT	ODP	16 1/2"	AF	CW	UBD	YES	MOTORIZED	EQ. SUPP. RAILS	C	1"	COOK CPS-A-165
UE-4	LASER ENGRAVER	500	1875	6	2	BELT	ODP	10"	BI	CW	UBD	YES	MOTORIZED	EQ. SUPP. RAILS	C	1"	COOK MH-70

IN-LINE EXHAUST FANS

UNIT NO.	SERVICE	CFM OF STD. AIR	EXT. S.P. IN IN. WATER	MAX. O.V. FPM	MOTOR HP	DRIVE	FAN DIA.	MOTOR TYPE	VOLUME CONTROL	SUPPORT	VIBRATION ISOLATORS		MANUF. MODEL
											TYPE	MIN. STATIC DEFLECT.	
IF-1	FCS LAB FLUSHING	2,500	0.75	900	1	DIRECT	1' - 3"	ODP	VFD	SUSPENDED	D	1"	COOK SQND-150

VARIABLE AIR VOLUME BOXES

BOX						HEATING COIL							
UNIT NO.	SERVICE	CFM OF STD. AIR	MIN. CFM OF STD. AIR	UPSTREAM DUCT SIZE	MAX. AIR P.D. IN IN. OF WATER	HEATING CFM OF STD. AIR	ENT. AIR TEMP.	LV. AIR TEMP.	ENT. H2O TEMP.	LV. H2O TEMP.	% PROP. GLYCOL	GPM	BRANCH PIPE SIZE	MANUF. MODEL
V-1	SCHOOL STORE A100A	300	90	6"Ø	1	300	55 °F	85 °F	160 °F	120 °F	0	0.5	1/2"	PRICE SDV
V-2	CLEANING A106	275	80	6"Ø	1	275	55 °F	85 °F	160 °F	120 °F	0	0.4	1/2"	PRICE SDV

ROOF EXHAUSTERS

UNIT NO.	SERVICE	CFM OF STD. AIR	MAX. SONES	EXT. S.P. IN IN. WATER	MOTOR HP	DRIVE	MOTOR TYPE	VOLUME CONTROL	DAMPER	SUPPORT	MANUF. MODEL
RE-1	WOODS LAB FLUSHING	3,000	14	0.5	0.75	DIRECT	ODP	VFD	BY B.A.S.	ROOF CURB	COOK ACRUD-195
RE-2	METALS LAB FLUSHING	3,000	14	0.5	0.75	DIRECT	ODP	VFD	BY B.A.S.	ROOF CURB	COOK ACRUD-195
RE-3	XAHU-8 O.A. RELIEF	1,650	17	0.5	0.75	DIRECT	ECPM	ECM/VFD	BY B.A.S.	ROOF CURB	COOK ACRUD-VF-165
RE-4	XAHU-8 ECONOMIZER RELIEF	9,700	23	0.5	3	DIRECT	ODP	VFD	BY B.A.S.	ROOF CURB	COOK ACRUD-270
RE-5	KITCHEN HOOD	3,100	20	1.5	2	DIRECT	ODP	VFD	NONE	ROOF CURB	COOK VCRD-180
RE-6	KITCHEN HOOD	2,500	17	1.5	2	DIRECT	ODP	VFD	NONE	ROOF CURB	COOK VCRD-180
RE-7	FCS LAB HOOD	2,200	21	1.5	2	DIRECT	ODP	VFD	NONE	ROOF CURB	COOK VCRD-165
RE-8	DISHWASH HOOD	1,000	21	1	0.5	DIRECT	ECPM	ECM/POT.	BY B.A.S.	ROOF CURB	COOK ACRUD-VF-150
RE-9	DISHWASH HOOD	1,000	21	1	0.5	DIRECT	ECPM	ECM/POT.	BY B.A.S.	ROOF CURB	COOK ACRUD-VF-150
RE-10	TOILET A107E AND LOCKERS A107D	250	7	0.5	0.167	DIRECT	ECPM	ECM/POT.	BY B.A.S.	ROOF CURB	COOK ACRUD-EC-90

HEAT EXCHANGERS

UNIT NO.	SERVICE	ENT. COIL TEMP.	LV. COIL TEMP.	% PROP. GLYCOL	GPM	BRANCH PIPE SIZE	ENT. H20 TEMP.	LV. H20 TEMP.	GPM	BRANCH PIPE SIZE	HEAT EXCH. TYPE	MAX. P.D. IN FT. WATER	MANUF. MODEL
HX-1	AHU-B2	120 °F	160 °F	35	13	1 1/4"	180 °F	140 °F	13	1 1/4"	PLATE	10	B&G BP405-50

NOTE: HX-1 IS UNDER ALTERNATE BID H1

CEILING EXHAUST FANS

UNIT NO.	SERVICE	CFM OF STD. AIR	TYPE	MAX. SONES	EXT. S.P. IN IN. WATER	MOTOR WATTS	MOTOR RPM	MOTOR TYPE	VOLUME CONTROL	MANUF. MODEL
CE-1	SMALL ANIMALS C128	150	CLG.	4	0.5	35 W	1675	ECPM	ECM/POT.	COOK GC-186
CE-2	AQUAPONICS C130	150	CLG.	4	0.5	35 W	1675	ECPM	ECM/POT.	COOK GC-186
CE-3	CUSTODIAN A106A	150	CLG.	4	0.5	35 W	1675	ECPM	ECM/POT.	COOK GC-186
CE-4	DATA C108	200	CLG.	6	0.5	60 W	1675	ECPM	ECM/POT.	COOK GC-186
CE-6	EL. EQUIP. A124	150	CLG.	4	0.5	35 W	1675	ECPM	ECM/POT.	COOK GC-186

IN-LINE PUMPS

UNIT NO.	SERVICE	SIZE	GPM	FEET OF WATER HEAD	MOTOR HP	MOTOR RPM	MOTOR TYPE	SUPPORT	MANUF. MODEL
IP-1	AHU-B2	1.25 x 1.25	13	30	0.5	3531	ECPM	PIPE	B&G XL 55-45
IP-2	AHU-5	1.25 x 1.25	22	30	0.5	3755	ECPM	PIPE	B&G XL 55-45
IP-3	AHU-6	1.5 x 1.5	57	30	1	2594	ECPM	PIPE	B&G XL 65-130
IP-4	AHU-10	1.25 x 1.25	9	30	0.5	3465	ECPM	PIPE	B&G XL 55-45
IP-5	AHU-11	1.5 x 1.5	37	30	1	2460	ECPM	PIPE	B&G XL 65-130
IP-6	RERU-1	1.25 x 1.25	9	30	0.5	3465	ECPM	PIPE	B&G XL 55-45
IP-7	RERU-2	1.25 x 1.25	5	30	0.5	3409	ECPM	PIPE	B&G XL 55-45
IP-8	BCU-1	1.25 x 1.25	8	30	0.5	3450	ECPM	PIPE	B&G XL 55-45
IP-9	BCU-2	1.25 x 1.25	6	30	0.5	3423	ECPM	PIPE	B&G XL 55-45
IP-10	BCU-3	1.25 x 1.25	3	30	0.16666	4141	ECPM	PIPE	B&G XL 36-45
IP-11	BCU-4	1.25 x 1.25	6	30	0.5	3423	ECPM	PIPE	B&G XL 55-45
IP-12	BC-5	1.25 x 1.25	19	30	0.5	3667	ECPM	PIPE	B&G XL 55-45
IP-13	BC-6	1.25 x 1.25	29	30	0.5	4012	ECPM	PIPE	B&G XL 55-45

NOTE: IP-1 IS UNDER ALTERNATE BID H1

COMBINATION FIRE/SMOKE DAMPERS

UNIT NO.	LOCATION	ASSOCIATED SYSTEM	DUCT SIZE IN (IN.)			SMOKE DETECTOR	OVAL CONN. REQ.	MANUF. MODEL
			WIDTH	HEIGHT	DIAMETER			
FSD-1	SERVERY A107B	AHU-10	42	24		YES	NO	RUSKIN
FSD-2	SERVERY A107B	AHU-10	36	24		YES	NO	RUSKIN
FSD-3	CONCESSION/CAFE A100B	XAHU-8	64	28		YES	NO	RUSKIN
FSD-4	CUSTODIAN A106A	AHU-10	36	24		YES	NO	RUSKIN
FSD-5	SERVERY A107B	TRANSFER	48	24		YES	NO	RUSKIN
FSD-6	OFFICE A121	RERU-2	28	16		YES	NO	RUSKIN
FSD-7	OFFICE A121	RERU-2	26	14		YES	NO	RUSKIN
FSD-8	FITNESS A133	RERU-2	16	10		YES	NO	RUSKIN
FSD-9	FITNESS A133	RERU-2	12	12		YES	NO	RUSKIN
FSD-10	FITNESS A134	RERU-2	12	12		YES	NO	RUSKIN
FSD-11	C.R. A126	RERU-2	12	12		YES	NO	RUSKIN
FSD-12	C.R. A126	RERU-2	16	10		YES	NO	RUSKIN
FSD-13	CONCESSION/CAFE A100B	XAHU-8	12	12		YES	NO	RUSKIN
FSD-14	SCHOOL STORE A100A	XAHU-8	12	12		YES	NO	RUSKIN
FSD-15	TOILET A107E	AHU-10	40	28		YES	NO	RUSKIN
FSD-16	MECHANICAL D173	XAHU-8	62	26		YES	NO	RUSKIN

BUFFER TANKS

UNIT NO.	SERVICE	TYPE	SYSTEM PIPE SIZE	TANK DIA.	TANK HEIGHT	CAPACITY GAL.	SUPPORT	MANUF. MODEL
BT-1	CHILLED WATER	VERT.	6"	30"	83"	211	CONC. PAD	TACO BTL
BT-2	CHILLED WATER	VERT.	6"	30"	83"	211	CONC. PAD	TACO BTL

EXPANSION TANKS

UNIT NO.	SERVICE	TYPE	TANK DIA.	TANK HEIGHT	CAPACITY GAL.	SUPPORT	MANUF. MODEL
EXP-1	HOT WATER	VERT.	36"	88"	317	CONC. PAD	B&G SERIES B
EXP-2	CHILLED WATER	VERT.	24"	55"	80	CONC. PAD	B&G SERIES B

DESTRATIFICATION FANS

UNIT NO.	SERVICE	CFM OF STD. AIR	FAN DIA	MOTOR WATTS	SOLID STATE SPEED CONTROLLER	BLADE HEIGHT A.F.F.	MANUF. MODEL
DS-1	ROBOTICS C116	3,861	4' - 0"	45 W	YES	18' - 0"	QMARK
DS-2	ROBOTICS C116	3,861	4' - 0"	45 W	YES	18' - 0"	QMARK

MAGNETIC AIR & DIRT SEPARATORS

UNIT NO.	SERVICE	SYSTEM PIPE SIZE	GPM	SUPPORT	MANUF. MODEL
MS-1	HOT WATER	5"	450	SUSPENDED	CALEFFI NA546M
MS-2	CHILLED WATER	6"	550	SUSPENDED	CALEFFI NA546M

WEATHERPROOF LOUVERS

UNIT NO.	SERVICE	NOM. WIDTH (IN.)	NOM. HEIGHT (IN.)	CFM	MAX FREE AREA VELOCITY (FPM)	MANUF. MODEL
WPL-1	FC-1	16	16	450	1,000	RUSKIN ELF6375DX
WPL-2	FC-2	16	16	500	1,000	RUSKIN ELF6375DX
WPL-3	FC-3	16	16	800	1,000	RUSKIN ELF6375DX
WPL-4	IF-1	48	16	2,500	1,000	RUSKIN ELF6375DX

UNDERCUT DOORS

ROOM NAME/NO.	SYMBOL	DESCRIPTION	HEIGHT OF UNDERCUT
TOILET A107E	UC	DOOR UNDERCUT	0' - 1"

VARIABLE FREQUENCY DRIVES

UNIT NO.	SERVICE	CONTROL TYPE	MANUF. MODEL
VFD-1	P-1	PRESS. DIFF. CONT.	ABB ACH-580
VFD-2	P-2	PRESS. DIFF. CONT.	ABB ACH-580
VFD-3	P-3	BALANCING	ABB ACH-580
VFD-4	P-4	BALANCING	ABB ACH-580
VFD-5	P-5	PRESS. DIFF. CONT.	ABB ACH-580
VFD-6	P-6	PRESS. DIFF. CONT.	ABB ACH-580
VFD-7	AHU-5	SZVAV	ABB ACH-580
VFD-8	AHU-6	SZVAV	ABB ACH-580
VFD-9	AHU-10	VAV	ABB ACH-580
VFD-10	AHU-11	VAV	ABB ACH-580
VFD-11	AHU-B2	BALANCING	ABB ACH-580

NOTE: PLEASE REFER TO THE MOTOR STARTERS SCHEDULE FOR MOTOR HP AND VOLTAGE REQUIREMENTS.

MOTOR STARTERS

DESCRIPTION	MCA	MOCP	MOTOR HP	VOLTAGE	PHASE	KW	STARTER FURNISHED BY	STARTER INSTALLED BY	STARTER LOCATION	STARTER TYPE	REMARKS
				120	1		HVAC	HVAC	PRE-WIRED	-	
AHU-5			20	480	3		HVAC	EC	NEAR UNIT	VFD	
AHU-6			15	480	3		HVAC	EC	NEAR UNIT	VFD	
AHU-10			15	480	3		HVAC	EC	NEAR UNIT	VFD	
AHU-11			30	480	3		HVAC	EC	NEAR UNIT	VFD	
AHU-B2			2	480	3		HVAC	EC	NEAR UNIT	VFD	
BAS-1	15	15		120	1		HVAC	HVAC	PRE-WIRED	-	
BCU-1			4.42	208	3		HVAC	HVAC	PRE-WIRED	ECM/VFD	UNIT HAS (2) ECPM MOTORS
BCU-2			4.42	208	3		HVAC	HVAC	PRE-WIRED	ECM/VFD	
BCU-3			0.75	208	3		HVAC	HVAC	PRE-WIRED	ECM/VFD	
BCU-4			4.42	208	3		HVAC	HVAC	PRE-WIRED	ECM/VFD	
CE-1				120	1	0.04	HVAC	HVAC	PRE-WIRED	ECM/POT.	
CE-2				120	1	0.04	HVAC	HVAC	PRE-WIRED	ECM/POT.	
CE-3				120	1	0.04	HVAC	HVAC	PRE-WIRED	ECM/POT.	
CE-4				120	1	0.06	HVAC	HVAC	PRE-WIRED	ECM/POT.	
CE-6				120	1	0.04	HVAC	HVAC	PRE-WIRED	ECM/POT.	
CH-1			0.2	120	1		HVAC	HVAC	PRE-WIRED	-	
CH-2			0.2	120	1		HVAC	HVAC	PRE-WIRED	-	
CH-3			0.2	120	1		HVAC	HVAC	PRE-WIRED	-	
CH-4			0.2	120	1		HVAC	HVAC	PRE-WIRED	-	
DC-1			30	480	3		HVAC	EC	NEAR UNIT		
DC-1 CONTROL PANEL	15	15		120	1		HVAC	HVAC	PRE-WIRED	-	
DS-1				120	1	0.05	HVAC	EC	NEAR UNIT	SP. SW.	
DS-2				120	1	0.05	HVAC	EC	NEAR UNIT	SP. SW.	
FC-1			0.25	120	1		HVAC	HVAC	PRE-WIRED	-	
FC-2			0.25	120	1		HVAC	HVAC	PRE-WIRED	-	
FC-3			0.25	120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-1				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-2				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-3				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-4				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-5				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-6				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-7				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-8				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-9				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-10				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-11				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-12				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-13				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-14				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-15				120	1		HVAC	HVAC	PRE-WIRED	-	
FSD-16				120	1		HVAC	HVAC	PRE-WIRED	-	
IF-1			1	208	3		HVAC	EC	NEAR UNIT	VFD	
IP-1			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-2			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-3			1	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-4			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-5			1	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-6			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-7			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-8			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-9			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-10			0.16666	120	1		HVAC	HVAC	PRE-WIRED	-	
IP-11			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-12			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
IP-13			0.5	208	1		HVAC	HVAC	PRE-WIRED	-	
MUA-1			10	480	3		HVAC	HVAC	PRE-WIRED	-	
MUA-2			5	480	3		HVAC	HVAC	PRE-WIRED	-	
P-1			15	480	3		HVAC	EC	NEAR UNIT	VFD	
P-2			15	480	3		HVAC	EC	NEAR UNIT	VFD	
P-3			10	480	3		HVAC	EC	NEAR UNIT	VFD	
P-4			10	480	3		HVAC	EC	NEAR UNIT	VFD	
P-5			25	480	3		HVAC	EC	NEAR UNIT	VFD	
P-6			25	480	3		HVAC	EC	NEAR UNIT	VFD	
RE-1			0.75	480	3		HVAC	HVAC	PRE-WIRED	VFD	
RE-2			0.75	480	3		HVAC	HVAC	PRE-WIRED	VFD	
RE-3			0.75	480	3		HVAC	HVAC	PRE-WIRED	ECM/VFD	
RE-4			3	480	3		HVAC	HVAC	PRE-WIRED	VFD	
RE-5			2	480	3		HVAC	HVAC	PRE-WIRED	VFD	
RE-6			2	480	3		HVAC	HVAC	PRE-WIRED	VFD	
RE-7			2	480	3		HVAC	HVAC	PRE-WIRED	VFD	
RE-8			0.5	120	1		HVAC	HVAC	PRE-WIRED	ECM/POT.	
RE-9			0.5	120	1		HVAC	HVAC	PRE-WIRED	ECM/POT.	
RE-10			0.167	120	1		HVAC	HVAC	PRE-WIRED	ECM/POT.	
RERU-1	15	20		480	3		HVAC	HVAC	PRE-WIRED	-	
RERU-2	15	20		480	3		HVAC	HVAC	PRE-WIRED	-	
UE-1			5	480	3		HVAC	HVAC	PRE-WIRED	VFD	
UE-2			3	480	3		HVAC	HVAC	PRE-WIRED	VFD	
UE-3			2	480	3		HVAC	HVAC	PRE-WIRED	VFD	
UE-4			2	480	3		HVAC	HVAC	PRE-WIRED	VFD	
UH-1			0.5	120	1		HVAC	EC	NEAR UNIT	MAN.	
UH-2			0.5	120	1		HVAC	EC	NEAR UNIT	MAN.	
UH-3			0.33	120	1		HVAC	EC	NEAR UNIT	MAN.	
UH-4			0.13	120	1		HVAC	EC	NEAR UNIT	MAN.	
VEF-1			1	208	3		HVAC	HVAC	PRE-WIRED	-	
VEF-2			1	208	3		HVAC	HVAC	PRE-WIRED	-	
XGFS-1	1	15		120	1		HVAC	HVAC	PRE-WIRED	-	
XUH-10			0.25	120	1		HVAC	EC	NEAR UNIT	MAN.	

WEATHERPROOF HOODS

UNIT NO.	SERVICE	TYPE	CFM OF STD. AIR	THROAT DIMENSIONS		MIN. HOOD FREE AREA (% OF THROAT AREA)	MIN. OPENING HEIGHT ABOVE ROOF	SUPPORT	MANUF. MODEL
				WIDTH	LENGTH				
WPH-1	AHU-10	INTAKE	10,000	3' - 0"	3' - 0"	200%	3' - 0"	ROOF CURB	COOK
WPH-2	BCU-2	INTAKE	2,800	2' - 0"	1' - 6"	200%	3' - 0"	ROOF CURB	COOK
WPH-3	BCU-3	INTAKE	1,725	1' - 6"	1' - 6"	200%	3' - 0"	ROOF CURB	COOK
WPH-4	BCU-4	INTAKE	2,800	2' - 0"	1' - 6"	200%	3' - 0"	ROOF CURB	COOK
WPH-5	AHU-5	INTAKE	15,700	4' - 0"	4' - 0"	200%	3' - 0"	ROOF CURB	COOK
WPH-6	AHU-6	INTAKE	12,500	3' - 6"	3' - 6"	200%	3' - 0"	ROOF CURB	COOK

VEHICLE EXTRACTION HOSE REEL AND FAN

UNIT NO.	SERVICE	CFM	HOSE DIAMETER	HOSE LENGTH	MOTOR HP	MANUF. MODEL
VEF-1	AUTOS LAB C121	600	5	34' - 0"	1	MONOXIVENT 9000 SERIES
VEF-2	AUTOS LAB C121	600	5	34' - 0"	1	MONOXIVENT 9000 SERIES

BRAY ARCHITECTS
Milwaukee
829 South 1st Street
Milwaukee, Wisconsin 53204
T: 414.226.0200
Sheboygan • Davenport
Moline • Saint Paul
www.brayarch.com

ENGINEERING DESIGN BY
MSA
(800) 362-4505 • www.msa-ps.com

Project Title:
ADDITION AND RENOVATIONS
WHITEWATER HIGH SCHOOL
WHITEWATER UNIFIED SCHOOL DISTRICT
534 S. ELIZABETH
WHITEWATER, WI 53190

ISSUANCES + REVISIONS:

	DATE	DESCRIPTION

Issued for:
CONSTRUCTION DOCUMENTS
12/19/2025

Project Number:
3705

Sheet Title:
SCHEDULES

Sheet Number:
H0.2

© 2024 Bray Associates Architects, Inc.

Autodesk Docs://3705 - Whitewater Unified School District Facility Master Planning 2024\0377241_Whitewater High School_HVAC_R24.rvt
12/18/2025 3:50:54 PM